

CIVIL ENGINEERING CALCULATOR

Staircase Material & Cost Report

Generated: 05 Jul 2026, 17:24

INPUT PARAMETERS

Design Dimensions:	150.0 mm, 250.0 mm
Width & Steps:	1200.0 mm x 10
Waist Slab:	150.0 mm
Concrete Mix:	1.0:2.0:4.0
Dry Factor:	1.54
W/C / Density:	0.5 / 2400.0 kg/m³
Bag Weight:	50.0 kg
Rates Applied:	C:10.0, S:20.0, A:50.0, Conc:60.0

QUANTITIES

Item	Quantity	Unit
Wet Volume	0.750	m³
Dry Volume	1.155	m³
Cement Bags	4.75	bags
Sand Volume	0.330	m³
Coarse Agg.	0.660	m³
Water Needed	118.8	L
Structure Weight	1799.486	kg

ESTIMATED COST

Cement Cost	47.51	\$
Sand Cost	6.60	\$
Aggregate Cost	32.99	\$
Other Concrete Cost	44.99	\$
TOTAL ESTIMATED COST	132.08	\$